

**PONCE DELEON INLET, FLORIDA
VOLUSIA COUNTY
NAVIGATION STUDY**

**FINAL FEASIBILITY REPORT
WITH FINAL ENVIRONMENTAL ASSESSMENT**

**U.S. ARMY CORPS OF ENGINEERS
JACKSONVILLE DISTRICT
JACKSONVILLE, FLORIDA**

JANUARY 1999

PONCE DELEON INLET, VOLUSIA COUNTY, FLORIDA
FINAL FEASIBILITY REPORT WITH FINAL ENVIRONMENTAL ASSESSMENT
SYLLABUS

A cooperative study has been conducted in response to a House Public Works and Transportation Committee resolution, dated May 21, 1991. The resolution requests review of the Corps reports pertaining to Ponce DeLeon Inlet to determine whether modifications to the recommendations presented in those reports are advisable. The reconnaissance report for the feasibility study was approved December 1993. In April 1994 funding was received to continue the feasibility phase of the study process. The purpose of the study is to determine the Federal interest in navigation improvements for the Ponce DeLeon Inlet Federal navigation project.

Problems addressed during the study include instability and erosion. These problems have created the need for frequent maintenance. They have also caused safety problems.

Early in the feasibility study navigation features that would satisfy planning objectives and constraints (measures) were identified. A no action plan was defined. The measures were combined into plans. The plans, referred to in the plan selection step of the formulation process as alternatives, were evaluated. The evaluation involved, in part, a comparison of alternative benefits and costs. Another round of evaluation took place after it was determined that there was no longer an opportunity for construction of a fishing park. The proposed fishing park had contributed both benefits and costs for the alternatives initially evaluated. The second round of evaluation included a refined no action (without project) alternative, a nonstructural alternative, and the alternative of construction of a 1,000-foot south jetty extension.

The selected plan would modify the existing Federal navigation project through construction of a 1,000-foot south jetty extension toward the ocean and parallel to the north jetty, with scour apron, placement of navigation aids, assumption of maintenance for the new work 1,000-foot ocean extension of the south jetty, with scour apron, and channel maintenance in natural deep water. The total initial cost of the selected plan is \$5,454,000, including construction and navigation aids. The currently estimated Federal share of the initial cost is \$2,988,000 and the non-Federal share is \$2,466,000. The currently estimated Federal share of the present worth value of operation, maintenance, repair, replacement and rehabilitation (OMRR&R) costs for the south jetty extension is \$35,000. The currently estimated non-Federal share of the present worth value of the OMRR&R costs for the south jetty extension is \$190,000.

Recommendations for modifications to the authorized project are the following: construction of a 1,000-foot south jetty extension toward the ocean and parallel to the north jetty, with scour apron; assumption of maintenance for the new work 1,000-foot ocean extension of the south jetty, with scour apron; and maintenance of channels in natural deep water.

This page intentionally left blank.

**PONCE DELEON INLET, FLORIDA
VOLUSIA COUNTY
FINAL FEASIBILITY REPORT**

TABLE OF CONTENTS

<u>Title</u>	<u>Page No.</u>
INTRODUCTION	1
STUDY AUTHORITY	1
STUDY PURPOSE AND SCOPE.....	1
PRIOR STUDIES AND REPORTS	2
WATER PROJECTS.....	6
PRIOR INLET HISTORY	6
EXISTING INLET PROJECT	6
OTHER NAVIGATION PROJECTS.....	9
PLAN FORMULATION.....	10
EXISTING CONDITIONS	10
PROBLEMS AND OPPORTUNITIES	13
PROSPECTIVE FUTURE CONDITIONS.....	20
ALTERNATIVE PLANS	30
PLANNING OBJECTIVES.....	30
CONSTRAINTS.....	31
CONSIDERED MEASURES FOR INLET STABILIZATION	32
PRELIMINARY ASSESSMENT	32
NUMERICAL/PHYSICAL MODEL TESTING	33
OTHER MEASURES	41
COMBINING MEASURES.....	54
ENVIRONMENTAL CONSIDERATIONS	77
MITIGATION RECOMMENDATIONS	85
ENDANGERED SPECIES	86
WATER QUALITY CERTIFICATION.....	87
INITIAL ALTERNATIVE EVALUATION	87
INITIAL BENEFIT ANALYSIS.....	89
INITIAL ECONOMIC SUMMARY	95
REFINED ALTERNATIVE EVALUATION.....	96
REFINED COST ESTIMATE.....	97
REFINED BENEFIT ANALYSIS.....	97
SENSITIVITY ANALYSIS	107
PLAN SELECTION	110

THE SELECTED PLAN	112
SOUTH JETTY SEWARD EXTENSION DESIGN	112
NAVIGATION AIDS	113
REAL ESTATE REQUIREMENTS	114
CONSTRUCTION	114
IMPACTS TO CHANNEL NAVIGABILITY CONDITIONS	114
IMPACTS TO SURFING	115
FIRST COSTS	115
FUTURE OPERATIONS AND MAINTENANCE	116
ANNUAL COSTS	117
ENVIRONMENTAL EFFECTS	118
BENEFITS	119
ECONOMIC SUMMARY	119
 PLAN IMPLEMENTATION	 120
PROJECT COOPERATION AGREEMENT	120
PRELIMINARY FINANCIAL ANALYSIS	121
DIVISION OF PLAN RESPONSIBILITIES	121
COST ALLOCATION	122
COST APPORTIONMENT	123
FEDERAL RESPONSIBILITY	124
NON-FEDERAL RESPONSIBILITY	124
ENVIRONMENTAL CONSIDERATIONS	126
FLOOD PLAIN ASSESSMENT	126
COASTAL ZONE BARRIER RESOURCES ACT	126
COASTAL ZONE MANAGEMENT ACT	127
 SUMMARY OF COORDINATION, PUBLIC VIEWS, AND COORDINATION	 127
CONCLUSIONS	127
RECOMMENDATIONS	129
DISCLAIMERS	132
REFERENCES	133
 ENVIRONMENTAL ASSESSMENT	

LIST OF FIGURES

<u>Figure No.</u>	<u>Title</u>	<u>Page No.</u>
1	Mosquito Inlet Survey	3
2	Existing Project	7
2a	Current Problem	15
3	Contour Plot Representation of 1994 Bathymetry	21
4	Change in Inlet Interior Bathymetry 1986 - 1994	23
5	MLW Shoreline Comparisons 1986, 1990, and 1994	25
6	Entrance Channel - Comparisons of Cross Sections.....	27
7	South Jetty Extension Lengths and Orientations.....	35
8	North Jetty Weir Opening Lengths.....	39
9	Channel Realignment	43
10	Revetment Alignments.....	45
11	The Selected Plan	47
12	North Spit and Commercial Vessel Facilities	51
13	Commercial Vessel Repair and Charter Operations.....	51
14	Groin Field	57
15	Plan G - Channel Deepening to IWW	61
16	Plan G - Channel Deepening to IWW	63
17	Plan G - Channel Deepening to IWW	65
18	Plan G - Channel Deepening to IWW	67
19	IWW Extension Plan Sheet.....	69
20	IWW Extension Plate 1	71
21	IWW Extension Plate 2	73
22	IWW Extension Plate 3	75
23	Maintenance Dredging Event Statistics	103
24	Ponce DeLeon Inlet Vicinity Dredging History	105

LIST OF TABLES

<u>Table No.</u>	<u>Title</u>	<u>Page No.</u>
1	Prior Studies and Reports.....	5
2	Waterborne Commerce	13
3	Ponce DeLeon Inlet New Work Costs and Maintenance	18
4	Deepening Volumes	59
5	Plan G Fishing Park Locations/Disposal Options	60
6	Commercial Fishing Facility Estimated First Costs	78
7	Alternative First Costs, IDC, Economic, Annual Costs	91
8	Benefit Summary	92
9	Comparison of Plan Benefits/Costs	92
10	Ponce DeLeon Inlet Maintenance Dredging Quantities	98

11 Intracoastal Waterway Maintenance Dredging	99
12 Interest During Construction	100
13 Maintenance Savings	107
14 Refined Alternatives.....	111
15 Plans A, F, & G14 Estimated Total First Costs	116
16 Economic Summary of Selected Plan.....	118
17 Cost Sharing Percentages.....	125
18 Cost Apportionment-First Costs.....	125
19 Cost Apportionment-O&M Costs.....	125

LIST OF APPENDICES

<u>Title</u>	<u>Appendix No.</u>
Engineering	A
Real Estate	B
Correspondence	C
Benefits.....	D
Photographs	E
Financing Plan and Statement of Financial Capability.....	F

SUPPLEMENTAL REPORTS

NUMERICAL MODEL REPORT (Taylor Engineering, Inc.)

Ponce DeLeon Inlet Feasibility Study Numerical Modeling and
Shoaling Analysis Volume I July 1966 (Chapters 1 - 6)

Ponce DeLeon Inlet Feasibility Study Numerical Modeling and
Shoaling Analysis Volume II July 1966 (Chapters 7 - 9)

Ponce DeLeon Inlet Feasibility Study Numerical Modeling and
Shoaling Analysis, Addendum 1 - ICWW Deepening and Flood
Sinus Evaluations

PHYSICAL MODEL REPORT (Coastal Engineering Research Center)

Physical Model Studies of Ponce DeLeon Inlet, Florida

ENGINEERING BENEFITS (Taylor Engineering, Inc.)

Ponce DeLeon Inlet Feasibility Study, Engineering Benefits
of the Proposed South Jetty Extension, July 1998