

FACT SHEET
COMPREHENSIVE EVERGLADES RESTORATION PLAN
Broward County Water Preserve Area
 Construction General (C)
 Congressional Districts: 20, 21, 22, 23, 24, 25

1. DESCRIPTION

This project is comprised of three (3) components: C-11 Impoundment, C-9 Impoundment, and Water Conservation Area (WCA) 3A/3B Levee Seepage Management which was authorized by the Water Resources Reform Development Act (WRRDA) 2014. The impoundment areas will 1) aid in reducing seepage from the WCA 3A/3B Seepage Management Area, 2) provide groundwater recharge, 3) provide additional water supply to urban areas, and 4) help prevent saltwater intrusion. The purpose of the WCA 3A/3B Levee Seepage Management system will focus on seepage reduction by allowing higher water levels in the L-33 and L-37 borrow canals. The purpose of the C-11 Impoundment is to direct runoff from the western C-11 drainage basin into the impoundment in lieu of pumping the untreated runoff via the S-9 Pump Station into the WCA 3A. If water is not available in the impoundment area to perform these functions, S-381 will be opened to allow seepage water to recharge the basin and prevent excessive dry outs. In addition, seepage will be collected and returned to the impoundment area. The purpose of the C-9 Impoundment is to pump runoff from the western C-9 drainage basin and diverted water from the western C-11 Basin into the impoundment. As a result, this impoundment will assist in reducing seepage from the WCA 3A/3B Levee Seepage Management.

2. FUNDING

Estimated Total Cost	\$1,081,210,000
Estimated Federal Cost	510,840,000
Allocation thru FY14	12,789,076
Carry In for FY15	2,000
Allocation for FY15	148,000
President's Budget FY16	2,900,000

3. SPONSOR

South Florida Water Management District
 3301 Gun Club Road
 West Palm Beach, Florida 334

4. STATUS

The Final Project Implementation Report and Chief's Report were signed on 21 May 2012. The Record of Decision was signed on 25 October 2012. The Chief's Report was transmitted to Congress on 26 October 2012. Preliminary design work is complete, and the project documentation has been updated to include changes in cost certification due to a minor change in the footprint in the recommended plan.

The Water Resources Reform and Development Act of 2014 (WRRDA 2014) authorized the project for construction. Cost recertification for FY2017 funding is underway. Efforts are underway to complete the design of the for the C-11 Impoundment project feature in order to award a construction contract in FY17.