

FACT SHEET

Intracoastal Waterway - Jacksonville to Miami, FL (O&M)

Operations & Maintenance

Congressional Districts: 3, 4, 5, 6, 7, 8, 17,18, 20, 21, 22, 23, 27

1. DESCRIPTION

The Intracoastal Waterway (IWW) project authorizes a channel 12 feet deep by 125 feet wide from Jacksonville, Florida south to Fort Pierce, Florida, and a channel 10 feet deep by 125 feet wide from Ft. Pierce, Florida south to Miami, Florida. The length of project is approximately 349 miles running from the St. Johns River in northeast Florida southward along the east coast to Miami, Florida.

2. FUNDING

Allocation for FY16	\$3,300,000
President's Budget FY17	\$850,000

3. SPONSOR

Florida Inland Navigation District (FIND)
 Mr. Mark Crosley, Executive Director
 561-627-3386
 1314 Marcinski Road
 Jupiter, Florida 33477-9427

4. STATUS

A Memorandum of Agreement with the Florida Inland Navigation District (FIND) to contribute funds for the Operation and Maintenance (O&M) of both the IWW and Atlantic Intracoastal Waterway (AIWW) was executed on 3 September 1997. Since that date, FIND has provided over \$50,000,000 for the O&M of the IWW and AIWW.

In FY15 dredging was completed within Indian River Reach 1. This dredge material is not suitable for beach placement and is being placed in a recently constructed Dredge Material Management Area (DMMA), IR-2. Funding for this dredging was shared between the Corps of Engineers and the FIND.

In FY16 plans and specifications and construction will be completed for DMMA O-7 which is located in Martin County, Florida. Funding for the plans and specifications is from Federal funding and construction of the DMMA will be from Contributed Funds from FIND. In addition, in FY16 investigations will be underway for Broward Reach 1, Crossroads and DMMA O-23. Dredging will occur within the St. Augustine and Matanzas reaches of the IWW and will be funded with Contributed Funds from FIND.



**INTRACOASTAL
WATERWAY (IWW)
JAX TO MIAMI**